

CHAPTER ST

STRUCTURES AND LAND RIG MOBILIZATION

Contents

Introduction	ST-1	Pre-inspection data review.....	ST-15
Rig nomenclature	ST-2	Inspection categories and limitations.....	ST-15
Drilling structures	ST-5	Documentation requirements.....	ST-16
Substructures	ST-6	Position of masts and derricks during	
Derricks and masts	ST-8	inspections	ST-18
Common characteristics	ST-9	Weld inspection performance and acceptance	
Personnel.....	ST-10	criteria	ST-18
Maintenance.....	ST-10	Inspection of repairs and modifications.....	ST-20
Objective.....	ST-10	Inspections and nondestructive	
Maintenance instructions.....	ST-11	examinations.....	ST-21
Safety summary	ST-11	Inspection of pad eyes, lifting eyes	
Routine inspections for maintenance	ST-11	and pin connections	ST-21
Periodic maintenance schedule	ST-11	Inspection of raising lines, guy lines	
Monthly maintenance	ST-12	and wire rope	ST-21
Yearly maintenance	ST-12	Inspection of racking platforms	ST-22
5-Yearly maintenance.....	ST-12	Inspection of substructures	ST-22
Periodic maintenance.....	ST-12	Report documentation and record	
Drilling structures	ST-12	requirements.....	ST-22
Guide track system.....	ST-12	Calibration requirements	ST-23
Drilling rig accessories	ST-12	Useful tools and equipment.....	ST-24
Bolts, bolted connections, and		Ethics and the inspector.....	ST-25
pins	ST-13	Safety	ST-25
Hoisting equipment.....	ST-13	Areas of concern.....	ST-25
High-pressure and other pipes.....	ST-13	Common work areas.....	ST-26
Personnel support devices.....	ST-13	Safety tie-off points.....	ST-26
Electrical equipment	ST-14	Dropped objects	ST-26
Wire rope/wireline, mast raising slings,		Storage of drilling structures	ST-26
hang-off lines	ST-14	Sheave assemblies	ST-27
Wind walls, other rig and drill floor		Short-term storage.....	ST-27
equipment	ST-14	Offshore masts and derricks	ST-27
Corrections and minor repairs.....	ST-14	Long-term storage.....	ST-27
Major repairs and modifications	ST-14	Racking boards and service platforms	ST-27
Maintenance not normally		Telescoping masts.....	ST-27
performed by user	ST-14	Cantilever masts.....	ST-28
Inspections.....	ST-14	References.....	ST-29
Qualification of personnel performing		Appendix: Land Rig Mobilization.....	ST-A1
inspections	ST-15		